EIELSON AIR FORCE BASE
ALASKA

RESTORATION ADVISORY BOARD MEETING

16 MARCH 2000

EIELSON AFB RESTORATION ADVISORY BOARD CO-CHAIRS

- EIELSON AFB - COL LARRY RESETER
- NORTH POLE - MR JOHN MAZZITELLO
- MOOSE CREEK - MS TERRY HUISMAN
- SALCHA - MR TOM PELUSO

ALASKA RAB CO-CHAIR ROUNDTABLE

DATE HELD: 8 - 9 FEB 2000

PLACE: ANCHORAGE, AK

TOPICS DISCUSSED:

- **OPEN DISCUSSION ABOUT RAB SUCCESS**
- **STORIES THROUGHOUT ALASKA**

FY00 FIELD SEASON ACTIVITIES

RUNWAY CLOSURE / REPLACEMENT

- WILL NOT IMPACT IRP SITES

FUEL HYDRANT PROJECT

- MINIMAL IMPACT TO IRP SITE ST-20, E-7 COMPLEX

FY00 FIELD SEASON ACTIVITIES

COMBAT INFORMATION TRANSPORTATION SYSTEM (CITS) PROJECT

- BASEWIDE FIBER OPTICS CABLE INSTALLATION PROJECT (MAY - SEPT 2000)
- WILL TRANSVERSE 12 IRP SITES

ST20	ST49	SS47	SS35
ST11	ST13	WP45	ST10
ST19	DP26	ST57	SS14

FY00 FIELD SEASON ACTIVITIES

CITS (CONTINUED)

- ENVIRONMENTAL WORKPLAN UNDER REVIEW BY ADEC AND EPA
- TRENCHING OPERATIONS / EXCAVATIONS MAY GENERATE CONTAMINATED SOILS, BOTH CERCLA AND RCRA REGULATED
- EXCESS SOILS WILL BE CHARACTERIZED FOR CONTAMINANT TYPES / LEVELS
- EXCESS SOILS WILL BE STOCKPILED AT THE LANDFARM FACILITY IAW ADEC GUIDANCE FOR LONG - TERM STOCKPILING, AWAITING DISPOSITION

FY00 FIELD SEASON ACTIVITIES

CITS (CONTINUED)

- HAZARDOUS WASTE CONTAMINANTS WILL BE STORED AT AND DISPOSED OF VIA THE HAZWASTE FACILITY
- POL CONTAMINATED SOILS ONLY WILL BE SENT TO OIT FOR REMEDIATION

FY00 FIELD SEASON ACTIVITIES

LTO - BIOVENTING SYSTEMS / SITEWIDE SAMPLING AND ANALYSIS PROGRAM

- OPERATION AND MAINTENANCE OF 5 BIOVENTING SYSTEMS
- ANNUAL BASEWIDE MONITORING
  - COE CONTRACT W/ BERING STRAITS ENVIRONMENTAL PENDING FINALIZATION

FY00 FIELD SEASON ACTIVITIES

NORTH BOUNDARY WELLS

- YEARLY SAMPLING AND CONFIRMATIONAL LAB ANALYSIS OF ANALYTES
- YEARLY FIELD MEASUREMENT OF STANDARD AQUIFER PARAMETERS (e.g... pH, CONDUCTIVITY, TURBIDITY, D.O, TEMP, TDS . ALKALINITY, WATER LEVEL)

FY00 FIELD SEASON ACTIVITIES

AOC's

- AOC 029 (BX SERVICE STATION AAA SITE).
  - PLACING OF ADDITIONAL MONITORING WELLS SCHEDULED TO FURTHER DELINEATE EXTENT OF DRO PLUME

- AOC 008 (EIELSON FARM ROAD AAA SITE PLUME DELINEATION)
  - CURRENT MODEL SHOWS FLOATING PRODUCT ENCOMPASSES APPROX. 5 ACRE AREA. ADDITIONAL MONITORING WELL(S) TO BE INSTALLED, MODEL USED TO RECALCULATE LATERAL EXTENT OF CONTAMINANT PLUME.

FY00 FIELD SEASON ACTIVITIES

- **FOLLOW-UP ACTION FOR AOC-008**

  FY2000 - CHARACTERIZE GROUNDWATER CONTAMINANTS UNDER EXISTING AOC CONTRACT

  FY2000 - CONVERT AOC-008 TO A FORMAL IRP SITE VIA THE SITE VALIDATION PROCESS

  FY2000 - PACAF TO DETERMINE IF SITE WILL BE PLACED INTO THE EIELSON AFB IRP OR INTO THE U.S. ARMY'S FUDS PROGRAM FOR ACTION

FY00 FIELD SEASON ACTIVITIES

SITE SS-001

- REPLACE TWO MONITORING WELLS REMOVED DURING FY99 BUILDING DEMOLITION
- CONTINUED LONG TERM MONITORING AND REGULATED SITE ACTIVITIES UNTIL DRO / RRO LEVELS ATTENUATE TO BELOW MCL's

690D

PROJECTED FY2001 ACTIVITIES

AOC-008

FY2001- PROGRAM FUNDING FOR CONTINUED INVESTIGATION

-- FILL DATA GAPS FROM THE LFI EFFORT

FY2001 - EIELSON AFB / ADEC TO REVIEW FIELD DATA AND PROPOSE REMEDIAL ACTION ALTERNATIVES TO PUBLIC

FY2002 - PROGRAM FUNDING FOR SELECTED REMEDIAL ACTION

PROJECTED FY2001 ACTIVITIES

- CONTINUED SITEWIDE SAMPLING AND ANALYSIS
- CONTINUED LONG - TERM OPERATIONS OF OU1 AND OU2 BIOVENTING SYSTEMS

PROJECTED FY2001 ACTIVITIES

- INITIATE AFCEE REMEDIAL PROCESS OPTIMIZATION (RPO) PROJECT
  - LTO / LTM OPTIMIZATION
  - TREATMENT SYSTEM PERFORMANCE REVIEWS
    -- TREND ANALYSIS OF ACTIVE BIOVENTING SYSTEM OPERATIONS
    --- PROJECT ESTIMATED TIMELINES FOR DECOMISSIONING ACTIVE TREATMENT SYSTEMS
  - DEVELOP DECISION TREE FOR CLOSURE OF QUALIFIED NFA SITES

OUTSTANDING FY99 ISSUE

OU2 AND OU 3, 4, 5 ROD AMENDMENTS

- EPA SIGNATURE - 30 Sept 98
- AIR FORCE SIGNATURE - 27 May 99
- ADEC SIGNATURE PENDING

QUESTIONS